

Calibration Plans for HAWC30


John A.J. Matthews

johnm@phys.unm.edu

University of New Mexico

Albuquerque, NM 87131

Calibration system: *Calibration Room (I)*





- Calibration systems are running at CSU and MTU
- To be ready for HAWC30:




1. complete the upgrade of MTU hardware:
 - (a) 3rd filter wheel
 - (b) 3rd radiometer (to monitor light to tanks)
 - (c) t_{start} and t_{stop} photo-sensors
2. upgrade the CSU control system: computer and software
3. be ready to ship the MTU system to Mexico
4. continue control software development and tank calibration studies at CSU

Calibration system: *Calibration Room (II)*




- Calibration room layout at the HAWC site:
 1. Current plan is for two electronics racks
 2. Will old Milagro racks meet our needs including good access from the sides?
 3. **Conduits** for the 600' fibers should terminate in the bottom of the *fiber patch panel* rack

Calibration system: *Excess Fiber Storage (I)*




- Excess 600' fiber will be stored in the ground just outside the calibration room
- We need to *upgrade* from what was done with the Milagro Outriggers:
 1. The fibers (cables) should be buried deeper
 2. Enclosure(s) need better drainage and cable management ...
- **Confirmation on the 600' length is needed!**

Calibration system: *Excess Fiber Storage (II)*




- Build a *Fiber Cable Vault* from e.g. two stock-tank(s):
 1. Access through a central man-hole
 2. Excess fiber is stored in a ~2'-wide annular region at the tank perimeter
 3. Conduits to the *calibration room* and to the *field enclosures* are mounted between the two (clam-shell) stock tanks

Calibration system: *field enclosure issues*





- The fiber connections in the *field enclosure* are now simple:
 1. Use commercial unions to connect the 600' fiber to one duplex 15m and two simplex 15m fibers
 2. **Excess 15m duplex fiber needs storage in this enclosure**
- Is the VAMOS *field enclosure* adequate for HAWC:
 1. Is there adequate space for 4 PMT cables and the optical fibers?
 2. Is the box buried deeply enough for temperature stability?

Calibration system: *tank issues*




- The optical diffuser will be attached to the central PMT:
 1. The float and diffuser have been prototyped at CSU
 2. The distance of the diffuser to the central PMT is now well defined
 3. **But how (precisely) will we attach the diffuser to the PMT ...**

Calibration system: *possible calibration patterns*




- Not a HAWC30 issue, but for HAWC100 etc ...
- Calibration optical switches map onto $1/15^{th}$ of the array:
 1. 10 DiCon switches allow us to illuminate 10 tank-pairs at one time
 2. Left: One option is to calibrate (20) contiguous tanks (at one time)
 3. Right: Another option is to distribute the calibrated tank-pairs over the array
 4. **Feedback please ...**

Calibration system: *timing signals (I)*



- Overview:
 1. the t_{start} pulse indicates that the laser has fired
 2. the t_{stop} pulse includes the *round trip time* delay and depends on the (current) setting of the DiCon GP700 switch
 3. **internal to the calibration system a BN1105 (universal frequency counter) uses the t_{start} and t_{stop} logic pulses to measure the *round trip time* to the tank optical diffuser**
 4. the prototype system at CSU results in a *round trip time* of ~ 2010 nsec

Calibration system: *timing signals (II)*



- Proposal:
 1. t_{start} is the (only) signal needed for our (CSU) analyses:
 - (a) the existence of the t_{start} TDC record indicates that this is a *calibration* event (*a.k.a.* trigger-less DAQ)
 - (b) PMT data are accepted in a timing window defined with respect to the t_{start} time
 - (c) relative times for low and high threshold signals are again defined with respect to the t_{start} time
 2. **HAWC calibration timing signals sent to the DAQ will be the logical AND of the internal timing signals with a *light to tanks* logic level signal**
 3. the *light to tanks* logic level is present **ONLY** when light is being sent to the tanks and is generated by the BN575 unit that also triggers the calibration laser

Calibration system: *timing signals (III)*

- Use the DAQ TDCs to monitor and cross check the calibration system:
 - digitize both the t_{start}^{DAQ} and t_{stop}^{DAQ} times ... requires 2 channels of TDC:
 1. measure the *round trip times*: $t_{stop}^{DAQ} - t_{start}^{DAQ}$
 2. compare with the same *round trip* light path measurement made with the BN1105 ... this is a cross check (consistency) of the TDC and BN1105 measurements
 3. step through different DiCon GP700 settings, *i.e.* different *round trip* light paths, to monitor the entire array
 - use a 3rd DAQ TDC channel to monitor the *light to tanks* logic pulse
 - reserve a 4th DAQ TDC channel for the possibility of one additional t_{stop}^{DAQ} signal

Calibration system: *timing signals (summary)*

- for clarity rename the calibration internal timing signals, t_{start} and t_{stop} as $t_{start}^{calibration}$ and $t_{stop}^{calibration}$
- define new signals, t_{start}^{DAQ} and t_{stop}^{DAQ} , which are the signals to be sent to the DAQ
- the calibration internal *light to tanks* signal and the internal timing signals are **AND**ed to form the two logic signals sent to the DAQ:

$$t_{start}^{DAQ} = t_{start}^{calibration} \cdot \textit{light to tanks}$$

$$t_{stop}^{DAQ} = t_{stop}^{calibration} \cdot \textit{light to tanks}$$

Calibration system: *HAWC30 additional parts*



- For HAWC30 we need additional parts:
 1. Overall *upgrade* from 1-tank to 30⁺-tank instrumentation
 2. Implement *minor* design changes based on CSU/MTU studies
 3. Address remaining issues ... e.g. *excess fiber storage*
- Several may involve 2⁺ month lead times ...
- **Highest priority: ordering and shipping ...**